



CITY STAMP:

W LAS ANIMAS ST



L=348.02'
 R=1045.92'
 Δ=23°21'53"



2 BASEMENT
 SCALE: 1/8" = 1'-0"

1 PREVIOUSLY AMMENDED SITE PLAN
 SCALE: 1/16" = 1'-0"



S SIERRA MADRE ST.

**MINOR AMENDMENT
 EXISTING SITE PLAN**

SITE ADDRESS:
 207 W LAS ANIMAS ST,
 COLORADO SPRINGS, CO 80903
 OWNER:
 PEACORE FAMILY LTD LIABILITY
 CO
 435 BROWN BEAR LN.
 COLORADO SPRINGS CO, 80906

APPLICANT:
bobbyhill
DESIGN
 210 WEST COCORDADO AVE.
 SUITE 308
 COLORADO SPRINGS, CO
 719-634-3600 719-639-2239

TAX SCHEDULE: 6419206039
 6419206062

LOT SIZE: 1.33 ACRES

LOT AREA: 57,935 SF

DATE: 03/23/2022

SHEET #

2

OF 10 SHEETS

FILE NO:DS MDP 96-315-A2M22

SITE INFORMATION:
 SITE ACREAGE:
 ACRES: 1.33 ACRES
 SQUARE FOOTAGE: 57,935 SF
 LOT COVERAGE
 SQUARE FEET: 13,625 SF (20%)
 BUILDING HEIGHT: 16'-0"
 BUILDING SQUARE FOOTAGE:
 MAIN LEVEL: 12,532 SF
 BASEMENT: 118 SF

CITY STAMP:

MINOR AMENDMENT PROPOSED SITE PLAN

SITE ADDRESS:
207 W LAS ANIMAS ST,
COLORADO SPRINGS, CO 80903

OWNER:
PEACORE FAMILY LTD LIABILITY
CO

435 BROWN BEAR LN.
COLORADO SPRINGS, CO, 80906

APPLICANT:
bobbyhill
DESIGN
210 WEST COOKS AVE
SUITE 308
COLORADO SPRINGS, CO
719-634-3600 719-639-2239

TAX SCHEDULE: 6419206039
6419206062

LOT SIZE: 1.33 ACRES

LOT AREA: 57,935 SF


DATE: 03/23/2022

SHEET #
3

OF 10 SHEETS
FILE NO: DS MDP 96-315-A2M22

W LAS ANIMAS ST 32'-5" R.O.W.

S SIERRA MADRE ST. 100'-0" R.O.W.



2 BASEMENT
SCALE: 1/8" = 1'-0"




GENERAL NOTES:
a. NO OPAQUE MESH OR WINDSCREEN
TO BE INSTALLED ON CHAIN LINK
FENCE.

PROPOSED SITE PLAN
SCALE: 1/16" = 1'-0"

CITY STAMP:

W LAS ANIMAS ST
32'-5" R.O.W.



.53'
92'
3'
40"

50.0' PROP. LINE

TRAINWREC
207 W. LAS ANIMAS ST.
(6419206039)

1 FLOOR PLAN- MAIN LEVEL/SITE
SCALE: 1/16" = 1'-0"



2 FLOOR PLAN- BASEMENT LEVEL
SCALE: 1/8" = 1'-0"

MINOR AMENDMENT
FLOOR PLANS

SITE ADDRESS:
207 W LAS ANIMAS ST,
COLORADO SPRINGS, CO 80903
OWNER:

PEACORE FAMILY LTD LIABILITY
CO
435 BROWN BEAR LN.
COLORADO SPRINGS CO, 80906

APPLICANT:
bobbyhill
DESIGN
210 WEST COCORDIA AVE.
SUITE 308
COLORADO SPRINGS, CO
719-634-3600 719-634-2239

TAX SCHEDULE: 6419206039
6419206062

LOT SIZE: 1.33 ACRES


LOT AREA: 57,935 SF

DATE: 03/23/2022

SHEET #

5

OF 10 SHEETS
FILE NO:DS MDP 96-315-A2M22



PLANT SCHEDULE					
QTY	ABREV.	BOTANICAL NAME / COMMON NAME	PLANTING SIZE	MATURE SIZE	IRRIGATION TYPE
3	KP	Koeleruteria paniculata / Goldenrain Tree	2' Cal.	25' X 25' H	DRIP X 4
8	JS	Juniperus Scopulorum 'Gray Glean' / Gray Glean Juniper	#15	6' X 15' H	DRIP X 3
Total Trees: 11					
QTY	ABREV.	BOTANICAL NAME / COMMON NAME	PLANTING SIZE	MATURE SIZE	IRRIGATION TYPE
9	Ccl	Caryopteris x clandonensis / Bluemist Spirea	#6	3' X 3' H	DRIP X 2
1	Jhh	Juniperus horizontalis 'Hughes' / Hughes Juniper	#5	6' X 2' H	DRIP X 2
Total Shrubs: 10					
QTY	ABREV.	BOTANICAL NAME / COMMON NAME	PLANTING SIZE	MATURE SIZE	IRRIGATION TYPE
42	App	Andropogon gerardi 'Wind Walker' / Windwalker Big Bluestem	#1	2' X 4'-6" H	DRIP X 1
15	Ckt	Calamagrostis brachytricha / Korean Feather Reed Grass	#1	2' X 4' H	DRIP X 1
Total Grasses: 57					
QTY	ABREV.	BOTANICAL NAME / COMMON NAME	PLANTING SIZE	MATURE SIZE	IRRIGATION TYPE
28	Hmc	Hemerocallis 'Stella de Oro' / Stella de Oro Daylily	#1	18" X 18" H	DRIP X 1
19	Pal	Perovskia atriplicifolia 'Little Spire' / Little Spire Russian Sage	#1	2'-3" X 2'-3" H	DRIP X 1
8	Rbk	Rudbeckia fulgida 'Goldsturm' / Black Eyed Susan	#1	18" X 24" H	DRIP X 1
19	Slv	Salvia x sylvestris 'Blue Queen' / Blue Salvia	#1	18" X 18" H	DRIP X 1
30	Vwv	Veronica lenensis / Turkish Veronica	F-15	18" X 2' H	DRIP X 1
Total Perennials: 104					

GROUND COVER SCHEDULE		
GROUND COVERS	QTY	NOTES
	1,085 sq. ft.	Rhizomatous Tall Fescue (Sod)
	710 sq. ft.	Shredded Cedar Mulch - 3" Depth
	1,445 sq. ft.	2" - 4" River Rock
	60 sq. ft.	Breeze - 3" Depth



$A=23'21.53"$
 $R=1045.92'$
 $L=348.02'$
 $C=423.57'$
 $D=5'28.40"$

TRAINWREC

207 W LAS ANIMAS ST
 COLORADO SPRINGS, COLORADO



719.600.8366
 john@urbanlandscapes.com

DEVELOPMENT PLAN -
 MINOR AMENDMENT


SHEET DATE: DECEMBER 31, 2021
 REVISION #1: 03/31/2022
 REVISION #2: 03/31/2022
 REVISION #3:

COPYRIGHT 2021
 This document is the intellectual property of the author and is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of the author.

NOT FOR CONSTRUCTION
 CITY FILE NUMBER DS MDP 96-315-A1M21


SHEET 06
 DP6
 FINAL LANDSCAPE PLAN

- NOTES:**
1. MARK THE NORTH SIDE OF TREE IN THE NURSERY, AND ROTATE TREE TO FACE NORTH AT THE SITE.
 2. AT TIME OF PLANTING, DO NOT REMOVE OR CUT LEAVES AND PRUNE ONLY DEAD OR BROKEN BRANCHES. CHECK OVER THE ENTIRE TREE FOR NARROW BRANCHES, LIMBS, OR DEFECTS. REMOVE NARROW BRANCHES, LIMBS, OR DEFECTS. PRUNE OR DO NOT REMOVE THE TERMINAL BUDDS OF BRANCHES THAT EXTEND TO THE EDGE OF THE CROWN.
 3. STRUCTURAL PRUNING SHOULD NOT BE DONE UNTIL THE ESTABLISHMENT PERIOD, USUALLY THE SECOND SEASON.
 4. PRUNE WITH CARE AND PREVENT DAMAGE TO BARK.
 5. DO NOT PRUNE FOR A LEAST ONE DECADAL PERIOD.
 6. REMOVE BRANCHES FROM THE CROWN OF THE TREE TO MAINTAIN AN OPEN, WELL-BRANCHED CROWN.
 7. WRAP TRUNK ON EXPOSED SIDES AND SPRINGS WITH TREE BARK. USE ELECTRICAL OR PLASTIC TAP, NOT TWINE.
 8. COORDINATE WITH CITY FORESTRY FOR CURRENT HEIGHT AND SPACING RECOMMENDATIONS PRIOR TO PLANTING.
 9. DEEP WATER ALL PLANTS AT TIME OF PLANTING.




1 DECIDUOUS TREE PLANTING DETAIL
NOT TO SCALE SECTION

- NOTES:**
1. PRUNE ONLY DEAD OR BROKEN BRANCHES AND WEAK OR NARROW CROTCHES.
 2. DEEP PLANTER MUST HAVE BRUSHED LATH PLANTING.
 3. DO NOT FERTILIZE FOR AT LEAST ONE GROWING SEASON.
 4. AMENDMENT BACKFILL SHALL BE 15 CM (6 INCH) PREFERENTIALLY CLASSIFIED AND 20 NATIVE AND/OR IMPORTED TOPSOIL.
 5. ALL SHRUBS IN ROCK AREAS TO RECEIVE 2\"/>



2 SHRUB PLANTING DETAIL
NOT TO SCALE SECTION


- NOTES:**
1. KEEP PLANTS MOIST AND SHADDED UNTIL PLANTING.
 2. PLANT GROUND COVER AND PERENNIALS LEVEL, 1/2\"/>



3 PERENNIAL/GROUNDCOVER PLANTING DETAIL
NOT TO SCALE SECTION

LANDSCAPE NOTES


1. PRIOR TO BEGINNING ANY WORK ON THE SITE, THE CONTRACTOR SHALL CONTACT THE OFFICE OF THE OWNER'S REPRESENTATIVE FOR SPECIFIC INSTRUCTIONS RELEVANT TO THE SEQUENCING OF WORK.
2. CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, TOOLS AND SERVICE NECESSARY TO FURNISH AND INSTALL ALL WORK SPECIFIED AND AS SHOWN ON THESE PLANS.
3. NO MATERIAL SUBSTITUTIONS SHALL BE MADE WITHOUT OWNER'S REPRESENTATIVE'S APPROVAL. ALTERNATE MATERIALS OF SIMILAR SIZE AND CHARACTER MAY BE CONSIDERED IF SPECIFIED PLANT MATERIALS CANNOT BE OBTAINED. OWNER'S REPRESENTATIVE RESERVES THE RIGHT TO REVISE PLANT LIST AS DEEMED NECESSARY.
4. THE SHOWN UTILITY LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE WORK. LOCATE EXACT UTILITY LOCATIONS BY CONTACTING "CALL BEFORE YOU DIG" AT (800) 922-1987. THE CONTRACTOR IS RESPONSIBLE FOR THE REPAIR OF ANY DAMAGE CAUSED TO UTILITIES.
5. AN EVENLY PLACED LAYER OF GRAVEL MULCH, COBBLE MULCH, OR BREEZE SHALL BE PLACED ON ALL AREAS DESIGNATED TO RECEIVE THE SPECIFIED MULCH. MINIMUM DEPTHS SHALL BE ACHIEVED IN ACCORDANCE TO THE SCHEDULE BY THE TYPE OF MULCH. WEED BARRIER FABRIC SHALL BE COMPLETELY COVERED AND PINNED.
6. AN EVENLY PLACED LAYER OF ORGANIC MULCH SHALL BE PLACED ON ALL AREAS DESIGNATED TO RECEIVE ORGANIC MULCH. ORGANIC MULCH SHALL BE APPLIED DIRECTLY TO TILLED, SCARIFIED, AMENDED AND UNCOMPACTED SOIL.
7. THE LANDSCAPE CONTRACTOR SHALL SUPPLY OWNER'S REPRESENTATIVE WITH A SAMPLE OF ALL TYPES OF MULCH FOR APPROVAL PRIOR TO INSTALLATION.
8. POROUS WEED BARRIER FABRIC SHALL BE INSTALLED IN ALL PLANTING BEDS ONLY IN LOCATIONS WHERE ORGANIC MULCH IS NOT PRESENT.
9. WEED BARRIERS SHALL BE A WOVEN, POROUS MAT AS MANUFACTURED BY AMERICAN EXCELSIOR POLYSPUN XL, DUPONT TYPAR STYLE 3341 OR MIRAFI "MIRASCAP". THE WEED BARRIER SHALL BE INSTALLED AS PER MANUFACTURER'S RECOMMENDATIONS. ALL WEED BARRIER SHALL BE COMPLETELY COVERED BY BREEZE.
10. 4" HEIGHT BY 3/16" WIDTH STEEL EDGING SHALL BE USED TO SEPARATE ALL PLANTING BEDS FROM VARYING TYPES OF TURF. PLACE EDGING FLUSH WITH GRADE. AVOID BROKEN BACK CURVES AND LONG TANGENTS BETWEEN CURVES. OBTAIN OWNER'S REPRESENTATIVE'S APPROVAL PRIOR TO INSTALLATION.
11. ALL EXISTING TOPSOIL IS TO BE STRIPPED AND STOCKPILED FOR USE IN PROPOSED LANDSCAPE. TOPSOIL SHOULD BE LOCATED WHERE IDENTIFIED ON THE CIVIL ENGINEERING GRADING AND EROSION CONTROL PLAN.
12. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING EXISTING EROSION CONTROL MEASURES AS PER THE CITY OF COLORADO SPRINGS SPECIFICATIONS DURING THE DURATION OF WORK ON-SITE.
13. CONTRACTOR SHALL PROVIDE 4" OF TOPSOIL AT ALL SOD AND PLANTING AREAS. GRADE SHALL BE ADJUSTED FOR SOIL THICKNESS. LANDSCAPE CONTRACTOR SHALL PERFORM ALL FINISH GRADING.
14. FOR PROPOSED SITE GRADING, SEE GRADING PLAN.
15. CULTIVATE THE SODDING BEDS AND SOD AREAS TO A DEPTH OF 12".
16. ALL PLANT MATERIALS SHALL HAVE BACKFILL CAREFULLY PLACED AROUND THE BASE AND SIDES OF BALL TO TWO-THIRDS (2/3) DEPTH OF THE BALL, THEN THOROUGHLY SOAK WITH WATER TO ALLOW SETTLEMENT. ALL WIRE, BURLAP FASTENERS AND BURLAP SHALL BE REMOVED AT THIS TIME. REMAINDER OF PIT SHALL THEN BE BACKFILLED, ALLOWING FOR DEPTH OF MULCH, SAUCER AND SETTLEMENT OF BACKFILL. BACKFILL SHALL THEN BE THOROUGHLY WATERED AGAIN.
17. ALL SHRUBS AND TREES SHALL BE PLANTED A MINIMUM OF 12" INSIDE OF ALL EDGING AND AWAY FROM WALLS AND OTHER PERMANENT STRUCTURES.
18. ALL PLANT LOCATIONS ARE APPROXIMATE; ADJUST AS NECESSARY TO AVOID CONFLICTS. OBTAIN OWNER'S REPRESENTATIVE'S APPROVAL OF LOCATIONS PRIOR TO PLANTING TREES AND SHRUBS.
19. QUANTITIES OF MATERIALS SHOWN ON THE PLANTING PLAN TAKE PRECEDENCE OVER QUANTITIES SHOWN ON THE PLANT MATERIAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL QUANTITIES ON THE PLANTING PLAN. REPORT ANY DISCREPANCIES IN THE PLANTING PLAN IMMEDIATELY TO THE OWNER'S REPRESENTATIVE.
20. ALL PLANT MATERIAL SHALL BE WELL-FORMED AND DEVELOPED IN GOOD CONDITION, HEALTHY AND DISEASE-FREE, AND BE TYPICAL OF THE SPECIES. PLANTS SHALL COMPLY IN ALL APPLICABLE RESPECTS WITH ACCEPTABLE STANDARDS AS SET FORTH IN THE COLORADO NURSERY ACT OF 1966 - TITLE 35, ARTICLE 25, CRS 1974 (SEE LANDSCAPE THE NURSERY ACT). OWNER AND OWNER'S REPRESENTATIVE RESERVES THE RIGHT TO REJECT AT ANY TIME OR PLACE PRIOR TO FINAL ACCEPTANCE OF WORK, ANY AND ALL PLANTS WHICH, IN THEIR OPINION, FAIL TO MEET THESE SPECIFICATION REQUIREMENTS.
21. PLANTS ARE TO BE SIZED AS SHOWN PER SPECIES ON THE PLANT SCHEDULE.
22. THE CONTRACTOR SHALL PROVIDE ALL WATER, WATERING DEVICES AND LABOR NEEDED TO IRRIGATE PLANT MATERIALS UNTIL PROVISIONAL ACCEPTANCE OF THE PROJECT. THE CONTRACTOR SHALL SUPPLY ENOUGH WATER TO MAINTAIN THE PLANTS' HEALTHY CONDITION.
23. ALL PLANT MATERIALS SHALL BE PROTECTED FROM THE DRYING ACTION OF THE SUN AND WIND AFTER BEING DUG, WHILE BEING TRANSPORTED, AND WHILE AWAITING PLANTING. BALLS OF PLANTS THAT CANNOT BE PLANTED IMMEDIATELY SHALL BE PROTECTED FROM DRYING ACTION BY COVERING THEM WITH MOIST MULCH. PERIODICALLY, APPLY WATER TO MULCH-COVERED BALLS TO KEEP MOIST. IF PLANTING SHOULD OCCUR DURING GROWING SEASON, APPLY ANTI-DESICCANT TO LEAVES BEFORE TRANSPORT TO REDUCE LIKELIHOOD OF WINDBURN. REAPPLY ANTI-DESICCANT AFTER PLANTING TO REDUCE TRANSPIRATION.
24. WRAP ALL TREE TRUNKS SPIRALLY WITH APPROVED WRAPPING MATERIAL FROM GROUND TO THE FIRST BRANCH. SECURELY TIE WRAPPING AT THE TOP AND BOTTOM WITH MASKING TAPE. TREES SHALL BE SUPPORTED IMMEDIATELY AFTER PLANTING IN THE MANNER SHOWN ON THE PLANTING DETAILS.
25. AFTER PLANTING IS COMPLETED, REPAIR INJURIES TO ALL PLANTS AS REQUIRED. LIMIT AMOUNT OF PRUNING TO A MINIMUM NECESSARY TO REMOVE DEAD OR INJURED TWIGS AND BRANCHES. PRUNE IN SUCH A MANNER AS NOT TO CHANGE NATURAL HABIT OR SHAPE OF PLANT. CENTRAL LEADERS SHALL NOT BE REMOVED.
26. FINE GRADE SOD AREAS TO ELIMINATE IRREGULARITIES ON THE SURFACE. ROLL OR PERFORM ADDITIONAL FINE GRADING.
27. ROLL SOD AFTER INSTALLATION TO ENSURE ROOTS ARE IN CONTACT WITH THE SOIL SURFACE. IMMEDIATELY BEGIN WATERING OF SODDING AREAS.
28. CONTRACTOR TO REMOVE TREE STAKES, TREE WRAP, AND ALL DEAD WOOD ON TREES AND SHRUBS ONE YEAR AFTER THE COMMENCEMENT OF THE PLANTING INSTALLATION.
29. AT THE COMPLETION OF PLANTING OPERATIONS ALL PLANTS SHALL BE INSPECTED BY THE OWNER AND OWNER'S REPRESENTATIVE. CONTRACTOR SHALL REPLACE IMMEDIATELY ANY PLANTS NOT IN HEALTHY AND VIGOROUS CONDITION AT THAT TIME AT NO EXPENSE TO THE OWNER. ANY PLANT NOT IN HEALTHY CONDITION DURING THE TWO-YEAR WARRANTY PERIOD SHALL BE REPLACED AS PER THE ORIGINAL SPECIFICATIONS, FREE OF CHARGE TO THE OWNER.
30. REMOVE ALL RUBBISH, EQUIPMENT AND MATERIAL AND LEAVE THE AREA IN A NEAT, CLEAN CONDITION EACH DAY. MAINTAIN PAVED AREAS UTILIZED FOR HAULING EQUIPMENT AND MATERIALS BY OTHER TRADES IN A CLEAN AND UNOBSTRUCTED CONDITION AT ALL TIMES.
31. THE FINISH GRADES AS SHOWN ON CIVIL CONSTRUCTION DRAWINGS SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM WALLS AND BUILDINGS.
32. THE TILLING OF PLANTING BEDS AND PLACEMENT OF BACKFILL IS TO OCCUR JUST PRIOR TO PLANTING; THEREAFTER, PROTECTION FROM COMPACTION AND CONSTRUCTION TRAFFIC SHOULD BE GIVEN.
33. 24 HOURS PRIOR TO PLANTING ALL PLANT MATERIAL, CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE TO INSPECT AND APPROVE THE PLANT LAYOUT LOCATIONS.
34. ALL EXISTING AND REPAIRED SOD AREAS TO HAVE A FULLY OPERATIONAL WORKING IRRIGATION SYSTEM. REPAIR/REPLACE ALL IRRIGATION COMPONENTS AS NEEDED.
35. IRRIGATION WILL BE PROVIDED TO ALL TREES, SHRUBS AND PERENNIALS VIA DRIP IRRIGATION. IRRIGATION WILL BE PROVIDED TO ALL AREAS OF TURFGRASS VIA SPRAY IRRIGATION.
36. MITIGATION OF EXISTING TREES MAY OCCUR WITHIN THE FLOODPLAIN OF THE SITE FOR SAFETY REASONS. TO ENSURE THE SAFETY OF THE USERS OF THE AREA, WEAK-WOODED PLANT MATERIAL AND DEAD/DYING PLANTS MAY BE REMOVED.
37. LANDSCAPE IMPROVEMENTS AND MAINTENANCE SHALL BE THE RESPONSIBILITY OF OWNER, AND/OR THEIR ASSIGNS.
38. ALL STREET TREES AND STREETSCAPE IMPROVEMENTS LOCATED IN THE ROW WILL BE MAINTAINED BY THE ADJUTING PROPERTY OWNER.
39. THERE ARE NO PROPOSED CHANGES TO THE SITE DRAINAGE.



4 TREE PROTECTION ZONE DETAIL
NOT TO SCALE SECTION

Appendix E: Schematic Landscape Diagram

To be submitted in conformance with Policy 311. (See reverse side for example.)



719.600.8366
john@urbanlandscapes.com

TRAINWREC
207 W LAS ANIMAS ST
COLORADO SPRINGS, COLORADO

**DEVELOPMENT PLAN -
MINOR AMENDMENT**

SUBMITTAL DATE: DECEMBER 30, 2021
REVISION #1: 03/10/2022
REVISION #2: 03/31/2022
REVISION #3: 03/31/2022
FOR CONSTRUCTION

NOT FOR CONSTRUCTION
CITY FILE NUMBER DS MDP 96-315-A1M21

SHEET 01 OF 09
DP7
LANDSCAPE NOTES & DETAILS

CITY STAMP:

MINOR AMENDMENT ELEVATIONS

SITE ADDRESS:

207 W LAS ANIMAS ST,
COLORADO SPRINGS, CO 80903

OWNER:

PEACORE FAMILY LTD LIABILITY
CO

435 BROWN BEAR LN.
COLORADO SPRINGS CO, 80906

APPLICANT:

bobbyhill
DE & T & NS
210 WEST COOKS ROAD
SUITE 308
COLORADO SPRINGS, CO
719-634-3600 719-639-2239

TAX SCHEDULE: 6419206039
6419206062

LOT SIZE: 1.33 ACRES

LOT AREA: 57,935 SF


DATE: 03/23/2022

SHEET #


9

OF 10 SHEETS


FILE NO:DS MDP 96-315-A2M22




4 SOUTH ELEVATION
SCALE: 3/16" = 1'-0"




7 TRASH ENCLOSURE SIDE
SCALE: 3/16" = 1'-0"




6 TRASH ENCLOSURE BACK
SCALE: 3/16" = 1'-0"




5 TRASH ENCLOSURE FRONT
SCALE: 3/16" = 1'-0"





3 WEST ELEVATION
SCALE: 3/16" = 1'-0"



2 NORTH ELEVATION
SCALE: 3/16" = 1'-0"



8 CHAIN LINK FENCE
SCALE: 3/16" = 1'-0"



1 EAST ELEVATION
SCALE: 3/16" = 1'-0"

